

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 7 Twp. 20S Rge. 19 (E) (W)

Location as "NE/CNW/SW" or footage from lines. SE SE SW  
Lease Owner National Cooperative Refinery Association  
Lease Name SCHNEIDER Well No. 2 SWD  
Office Address 305 Rule Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Disposal Well  
Date well completed June 3, 1955  
Application for plugging filed June 12, 1962  
Application for plugging approved June 14, 1962  
Plugging commenced Aug. 6, 1962  
Plugging completed Aug. 9, 1962  
Reason for abandonment of well or producing formation Producers utilizing this well were abandoned.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4330 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	492'	None-Cemented
				5-1/2"	4328'	2492'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with sand from 4300' to 4240'. Mixed and dumped 5 sacks of cement from 4240' to 4200'. Pulled casing. Mudded hole to 410'. Set 10' rock bridge from 410' to 400'. Mixed and dumped 30 sacks of cement from 400' to 310'. Mudded hole from 310' to 350'. Set 5' rock bridge from 35' to 30'. Mixed and dumped 10 sacks of cement from 30' to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 21 1962  
CONSERVATION DIVISION  
Wichita, Kansas  
8-21-1962

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor ACE PIPE PULLING CO.  
Address P. O. Box 304, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. R. Sears (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears (C. R. Sears)  
305 Rule Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of August, 1962

Neil McComb  
Notary Public.

My commission expires November 26, 1964



9

COMPANY National Cooperative Refinery Association

SEC. 7 T. 20 R. 19W  
 LOC. SE SE SW

FARM Schneider NO. 2

TOTAL DEPTH 4330'

COUNTY Pawnee

COMM. 4/12/55


COMP. 4/27/55

KANSAS

SHOT OR TREATED

CONTRACTOR M. B. Armer

ISSUED



CASING

20	10	
15	8	492'
12	6	
13	5	4328'

ELEVATION 2259 K.F.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay	40
Shale & Shells	200
Shale, Streaks of Sand	260
Sand	330
Blue Shale	450
Sand, Streaks of Shale	492
Blue Shale	630
Red Bed	820
Sand	1050
Red Bed & Shells	1410
Anhydrite	1440
Shale & Shells	2140
Lime	2265
Shale & Lime	2313
Lime	2550
Broken Lime	2670
Shale & Lime	3520
Lime	3570
Shale & Lime	3626
Lime	4115
Shale & Lime	4173
Lime	4223
Shale & Lime	4228
Shale & Lime	4330

RECEIVED  
 STATE CORPORATION COMMISSION

JUN 13 1962

CONSERVATION DIVISION  
 Wichita, Kansas

FORMATION TOPS

HEBENR	3714
LANSING	3764
BASE KANSAS CITY	4103
CONGLOMERATE	4234
CONGLOMERATE SAND STONE	4258
MISSISSIPPI	4322

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

M. B. ARMER

By *[Signature]*

STATE OF KANSAS  
 SS:  
 COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 28th day of April, 1955.

*[Signature]*  
 Notary Public

My Commission Expires - February 13, 1956.