



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Tom Altm of Proencer Wdg. Inc has this date requested permission to plug the following described well:

Operator's Full Name: Liberty Enterprises, Inc.

Complete Address: 308 West Mill; Plamville, Mo. 67463

Lease Name: Seltman Well No. #1

Location: C-NW-NW Sec. 11 Twp. 20<sup>S</sup> Rge. 20<sup>W</sup> (E) (W)

County: Pawnee Total Depth: 4250<sup>FE</sup>

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Altm. was instructed to plug the well as follows:

8 7/8" 252<sup>EL</sup> SP. CMC w/150<sup>SE</sup> Cement-2% Gel. 3% CaCl.  
Order 110<sup>SE</sup> 50/50 Pozmix 4% Gel. + 8 7/8" Plug  
spot With Drill Stem - With Heavy mud Between all plugs.  
1<sup>st</sup> Plug. @ 680<sup>EL</sup> w/ 65<sup>SE</sup> Cmt.  
2<sup>nd</sup> Plug. @ 270<sup>EL</sup> w/ 30<sup>SE</sup> Cmt.  
3<sup>rd</sup> Plug. -> Solid Bridge - Plug @ 40<sup>EL</sup> 100<sup>SE</sup> w/10<sup>SE</sup> Cmt.  
5<sup>th</sup> In Pat Hole Very truly yours, (By allied Cmt.)

Marian Schmidt  
Conservation Division Agent

MAR 16 1981