



15.145.20733.0000

JOHN CARLIN
R. G. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Bill Roach of Husky Drilg. has this date requested permission to plug the following described well:

Operator's Full Name: Kansas Petroleum Inc.

Complete Address: Suite 100-200 East 1st Wichita, Ms. 67202

Lease Name: Dick Well No. #1

Location: C-SE-NW-SW Sec. 15 Twp. 20 Rge. 20 (W)

County: Pawnee Total Depth: 4340 FT

Abandoned Oil Well Gas Well Input Well SWD Well DSA

Other well as hereafter indicated: _____

Mr. Roach was instructed to plug the well as follows:

8 5/8" 265 FT SP. cml w/200 ST 50/50 Pozmix - 2% Gel. 3% Ca-Cl
Order 110 ST 50/50 Pozmix 4% Gel. + 8 5/8" Plug - Elev. 2236 G.L.
Spot with Drill Stem - With Heavy Mud between all Plugs.
1st Plug @ 680 FT w/ 70 ST Cmt.
2nd Plug @ 240 FT w/ 25 ST Cmt.
3rd Plug -> Solid Bridge - Plug @ 40 FT 0 w/ 10 ST Cmt.
5th In. Rat Hole.

Very truly yours, (By Halliburton)

Merion Schmed
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
NOV 26 1980
CONSERVATION DIVISION
Wichita, Kansas