



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Buchheister of J. O. Farmer has this date requested permission to plug the following described well:

Mr. Buchheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Inc.

Complete Address: 370 W. Wichita Ave. Russell, Kansas

Lease Name: George Miller Well No. 1

Location: C SW NW Sec. 20 Twp. 20 Rge. (E)(W) 20

County: Pawnee Total Depth 4372' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Buchheister was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 550' and displace
70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. J. Massey
Conservation Division Agent