



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. - 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 28 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Burris of Chief Drilling Co. has this

date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Co. Inc.,

Complete Address: Box 797 Great Bend, Kansas

Lease Name: Helms Well No. 1

Location: SE SE Sec. 16 Twp. 20 Rge. 20 (E) (W) X

County: Pawnee Total Depth 4357 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buriss was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace
70 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Leo J. M...f
Conservation Division Agent