

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-26348-00-00
Spot: NESWSWNW Sec/Twnshp/Rge: 3-29S-14E
3283 feet from S Section Line, 4713 feet from E Section Line
Lease Name: R COMPTON TRUST Well #: B1-3
County: WILSON Total Vertical Depth: 1285 feet

Operator License No.: 33539
Op Name: CHEROKEE WELLS LLC
Address: 5201 CAMP BOWIE BLVD STE 200
FT WORTH, TX 76107

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1279		130 SX
SURF	8.625	41		8 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 12/05/2017 10:00 AM
Plug Co. License No.: 99975 Plug Co. Name: COMPANY SERVICING TOOLS
Proposal Rcvd. from: JEFF MORRIS Company: CHEROKEE WELLS LLC Phone: (620) 378-3650

Proposed Plugging Method: Set 50' 50/50 Poz blend cement plug on TD to approx. 1235'. Fill to approx. 600' with 9# (minimum) bentonite gel, then set 50' cement plug to approx. 550'. Fill with gel to approx. 150', then cement to surface.

Plugging Proposal Received By: ALAN DUNNING Witness Type: PARTIAL
Date/Time Plugging Completed: 12/05/2017 10:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

Run tubing to 1265 ft and pump fresh water to surface to establish circulation. The hole was gelled with 10 bbls of bentonite gel. 10 sacks of pozmix cement were then pumped at TD. 20 joints of tubing were removed and 10 sacks of pozmix cement spotted from 640 ft to 590 ft. The tubing was pulled to 191 ft and the well pumped full of pozmix cement. According to operator, a total of 40 sacks of cement were used to plug well.

RECEIVED
KCC DIST # 3
DEC 20 2017
CHANUTE, KS

AD

INVOICED

JAN 18 2018

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)