

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19350-00-00
Spot: SENESE Sec/Twnshp/Rge: 30-31S-6E
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: BURDEN UNIT Well #: 16-5
County: COWLEY Total Vertical Depth: 2976 feet

Operator License No.: 30169
Op Name: DOUBLE "D" OIL COMPANY, INC.
Address: 2009 JEAN CT
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.1875	2882		0 SX
SURF	6.625	2012		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/19/2017 8:00 AM
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL AND/OR PENNY M. DBA MCPHERSON DRILLING
Proposal Revd. from: DON BUTLER Company: _____ Phone: (620) 221-3570

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 12/21/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2830', DUMP BAILED 5 SX CEMENT ON TOP OF SAND. ~~7290'~~ @ 2790'. RIH W/PLUG @ 477', SANDED WELL BACK @ 450' W/1 SX CEMENT. TOGGED PLUG @ 435'. RIH W/WIRLINE & PERFORATED @ 430'-431' (2 HOLES). RIH W/WIRELINE PERFORATED AT 351'-351' (2 HOLES). 12-20-2017 RIH W/TUBING @ 430', DOUBLE D MIXED & PUMPED 12 SXS CLASS A COMMON & DISPLACED IN CASING. 12-21-2017 RIH W/TUBING @ 350', DOUBLE D ESTABLISHED CIRCULATION AND PUMPED 55 SXS CLASS A COMMON TO SURFACE. LAYED DOWN TUBING. SWEDGED INTO 5 1/2" & PUMPED 65 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. DANIELS READY MIX #38955 & 38957. TOTAL 120 SXS.

Perfs:

Top	Bot	Thru	Comments
2882	2976	CSG	

INVOICED
JAN 18 2018

Remarks: COMPLIANCE/ 10 YEAR TA

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

✓
JK