

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-20705-00-00  
Spot: E2SESW Sec/Twnshp/Rge: 3-19S-6W  
660 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: BURKE Well #: 1  
County: RICE Total Vertical Depth: 3325 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 522 N. MAIN ST PO BOX 560  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3334	1200	50 SX
SURF	8.625	214		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/22/2017 12:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: \_\_\_\_\_ Phone: (620) 583-5527

Proposed Plugging Method: In accordance with the rules and regulations of the KCC

Plugging Proposal Received By: JERRY SPARLING Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/29/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Sanded back to 3200' capped with 5 sx cement. Cut casing off at 1230' and pulled casing out of hole. Tripped tubing into 950' pumped 35 sks common 3% cc. Waited 1.5 hours and tagged plug @600'. TTIH to 2nd plug @500' 35 sx common 3% cc 3rd plug TTOH to 265' circulated to surface w/ 130 sx 60/40 poz 2% gel good returns cement to surface.

Perfs:

Top	Bot	Thru	Comments
3286	3295		

Remarks: MIRU COPELAND CEMENT OUT OF GREAT BEND

INVOICED

JAN 18 2018

Plugged through: CSG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

