

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-21640-00-00
Spot: SESWSW Sec/Twnshp/Rge: 3-19S-6W
330 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BURKE Well #: 2
County: RICE Total Vertical Depth: 3325 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3324		100 SX
SURF	8.625	214		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/23/2017 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: _____ Phone: (620) 583-5527

Proposed Plugging Method: In accordance with the rules and regulations of the KCC

Plugging Proposal Received By: JERRY SPARLING Witness Type: PARTIAL
Date/Time Plugging Completed: 09/22/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Sanded back to 3000' capped with 5 sx cement. Cut casing off at 1600' and pulled to 950' pumped 35 sks common 3% cc. Waited 2 hours and tagged plug @ 800'. Pulled casing to 2nd plug @ 500' 35 sks common 3% cc 3rd plug @ 265' circulated to surface w/ 30 sks common 3% cc and 75 sxs 60/40 poz 2% gel good returns cement to surface 175 sks total cement job complete.

Perfs:

Top	Bot	Thru	Comments
3275	3287		
3091	3112		

Remarks: MIRU COPELAND CEMENT OUT OF GREAT BEND

Plugged through: CSG

INVOICED
JAN 18 2018

District: 02

Signed

B. J. Hope

(TECHNICIAN)



✓ JK