

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-20427-00-00
Spot: SENWSW Sec/Twnshp/Rge: 31-33S-12E
1611 feet from S Section Line, 4582 feet from E Section Line
Lease Name: BRUEN RIGDON BRUEN Well #: 36
County: CHAUTAUQUA Total Vertical Depth: 1146 feet

Operator License No.: 5970
Op Name: ELMORE, JOHN A. OR PATRICIA R.
Address: 776 HWY 99
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1142		20 SX
SURF	6.25	767		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/15/2017 2:00 PM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: ELMORE'S INC. Company: _____ Phone: (620) 249-2519

Proposed Plugging Method: Well was squeezed in 1997 from 750' to surface with 150 sacks cement. Run 1" to 1100' Gel hole spot 5 sacks cement Pull up to 700'. Spot 5 sacks pull up to 275' cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 12/15/2017 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 980' gelled hole and spotted 5 sack plug. Pulled up to 700' and spotted 5 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 40 sacks of cement were used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
JAN 02 2018
CHANUTE, KS

INDEXED
JAN 16 2018

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)