

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-30808-00-00
Spot: SESESE Sec/Twushp/Rge: 15-34S-14E
362 feet from S Section Line, 346 feet from E Section Line
Lease Name: BETTS Well #: 1-15
County: MONTGOMERY Total Vertical Depth: 1539 feet

Operator License No.: <u>32353</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>GATEWAY RESOURCES U.S.A., INC.</u>	PROD	4.5	1534		
Address: <u>1821 ARBOR DR</u> <u>BARTLESVILLE, OK 74006</u>	SURF	8.625	22		
	T1	2.375	1475		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 12/29/2017 2:00 PM
Plug Co. License No.: 4836 Plug Co. Name: AXTHELM, DONALD W. DBA A-I WELL SERVICE
Proposal Revd. from: MARTIN CUMMINGS Company: GATEWAY RESOURCES U.S.A., IN Phone: (918) 914-9033

Proposed Plugging Method: Per KCC regulations

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 12/29/2017 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Bridge plug set at 840'. On December 22, 2017 ran 1" to 840' and spotted 10 sack plug. Pulled 1" out of well. On December 29, 2017 ran 1" in well and tagged cement at 690'. Pulled up to 250' and circulated cement to surface. Pulled 1" and topped well off. A total of 16 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1463	1465		
1076	1077		
1068	1069		
1038	1042		

INVOICED
JAN 17 2018

RECEIVED
KCC DIST # 3
JAN 02 2018
CHANUTE, KS


INVOICED
JAN 17 2018

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC

Plugged through: TBG

District: 03

Signed _____



(TECHNICIAN)