

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21569-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 19-32S-9W
510 feet from N Section Line, 330 feet from W Section Line
Lease Name: RICKE Well #: 1-19
County: HARPER Total Vertical Depth: 4464 feet

Operator License No.: 5429
Op Name: HAYES OIL & GAS LLC
Address: 1081 W HWY 160 PO BOX 108
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4464		125 SX
SURF	8.625	252		180 SX
T1	2.875	4347		

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/21/2017 12:00 AM
Plug Co. License No.: 34422 Plug Co. Name: RED ROCK ENERGY SERVICES INC.
Proposal Rcvd. from: SHAYNE G HAYES Company: RED ROCK ENERGY SERVICES Phone: (620) 254-7204

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/25/2017 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

RAN TUBING TO 4200' & SPOTTED 30 SKS CEMENT. TOH WITH TUBING. SHOT OFF & RECOVERED CASING FROM 2395'. TIH WITH TUBING TO 1500', SPOT 35 SX CEMENT, TAGGED CEMENT AT 1400'. TOH WITH TUBING TO 900' & SPOTTED 35 SX CEMENT. TOH WITH TUBING TO 300' & CIRCULATED HOLE WITH 120 SX CEMENT. TOH WITH TUBING & TOP OF CEMENT WITH 10 SKS CEMENT.

Perfs:

Top	Bot	Thru	Comments
4400	4401		
4364	4365		
4333	4354		


INVOICED
JAN 17 2018

Remarks: BASIC ENERGY SERVICES

Plugged through: TBG

District: 02

Signed _____



(TECHNICIAN)

✱