

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-22000-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 21-23S-13E
300 feet from S Section Line, 330 feet from W Section Line
Lease Name: JONES Well #: 24
County: GREENWOOD Total Vertical Depth: 2089 feet

Operator License No.: 33640
Op Name: HAAS PETROLEUM, LLC
Address: 10551 BARKLEY ST. #307
OVERLAND PARK, KS 66212

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2071		125 SX
SURF	8.625	32		8 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/20/2017 12:00 PM
Plug Co. License No.: 33557 Plug Co. Name: SKYY DRILLING, LLC
Proposal Rcvd. from: HAAS PETROLEUM, LLC Company: _____ Phone: (913) 499-8373

Proposed Pumping Method: Pump full of cement from top to bottom

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/20/2017 4:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 1665', pumped 20 sxs cement, pulled tubing to 800', pumped 20 sxs cement, pulled tubing to 250', pumped 45 sxs cement to surface, gel spacers between cement plugs.

Perfs:

RECEIVED
KCC DIST # 3
DEC 26 2017
CHANUTE, KS

MH

INVOICED
JAN 17 2018

Remarks:
Plugged through: TBG

District: 03

Signed Michael Heffern
(TECHNICIAN)



PRESSURE PUMPING LLC
 PO Box 884, Chanute, KS 66720
 620-431-9210 or 800-467-8676

TICKET NUMBER 53945

LOCATION Ottawa KS

FOREMAN Fred Maden

FIELD TICKET & TREATMENT REPORT
 CEMENT

15-673-22000

DATE	CUSTOMER #	WELL, NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY	
12-20-17	3451	Jones # 24	SE 21	Q3	13	GW	
CUSTOMER Haas Petroleum & Mark Hays							
MAILING ADDRESS 10551 Barkley St #307							
CITY Overland Park							
STATE KS							
ZIP CODE 66212							
TRUCK #		DRIVER		TRUCK #		DRIVER	
712		Fre Mad					
495		Har Ber					
548		Mike Hays					

JOB TYPE Plug HOLE SIZE — HOLE DEPTH — CASING SIZE & WEIGHT 4 1/2"
 CASING DEPTH 1665' DRILL PIPE 1" TUBING TO 1665' OTHER —
 SLURRY WEIGHT — SLURRY VOL — WATER gal/sk — CEMENT LEFT in CASING Full
 DISPLACEMENT N/A DISPLACEMENT PSI — MIX PSI — RATE 1-1 1/2 BPM

REMARKS: Hold Safety meeting. Rig ran 1" tubing to T₂ @ 1665' spot 20 SKS
Cement. Get hole to 800' pull 1" to 800' spot 20 SKS cement
Get hole to 250'. Pull 1" tubing to 250'. Fill to surface w/ cement
Put remaining 1" tubing. Top off well w/ cement. Wash out
1" pipe. Top off Well #32. w/ dry cement (Plugged 12/15/17)

Customer Supplied Washer
McCoy's Mike McFron Fred Maden

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE	495	1500 ⁰⁰
CE0002	35	MILEAGE	495	250 ²⁵
CE074	Minimum	Ten Miles Delivery	548	660 ⁰⁰
			Sub Total	2410 ²⁵
			less 30%	1687 ¹⁸
CE5840	755SKS	Poc. Blend I B Cement		10125 ⁰⁰
CE5965	778*	Baritanite Gel		2233 ⁴⁰
			Sub Total	1245 ⁵⁰
			less 30%	872 ¹³
			7.5%	SALES TAX
				65 ⁴¹
				ESTIMATED TOTAL
				2624 ⁷³
				(3749 ⁵⁷)

RAVIN 5737

AUTHORIZATION _____ TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.