

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-05763-00-00
Spot: SENWSW Sec/Twnshp/Rge: 32-13S-14W
1650 feet from S Section Line, 4290 feet from E Section Line
Lease Name: H BOXBERGER Well #: 3
County: RUSSELL Total Vertical Depth: 3300 feet

Operator License No.: 31250
Op Name: HUXMAN, RICHARD LEON DBA KSC O
Address: PO BOX 567
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3300		150 SX
SURF	8.625	904		400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/15/2017 8:30 AM
Plug Co. License No.: 35321 Plug Co. Name: THUNDER ROUSTABOUT, INC.
Proposal Rcvd. from: LEON HUXMAN Company: HUXMAN, RICHARD LEON DBA K Phone: (785) 483-0567

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 8 sx gel and 400 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/15/2017 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1425', 904' and 375'. Ran tubing to 3011' and pumped 8 sx gel followed by 75 sx cement w/200 # hulls. Pulled tubing to 1450' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 450' and pumped 45 sx cement. Circulated cement to the pit. Shut valve on casing. Hooked to braden head and pumped 60 sx cement. Circulated cement out of braden head and shut in. POOH. Topped off with 10 sx cement. Hole stayed full.

GPS: 38.87580 -098.90657

Perfs:

Remarks: QUALITY CEMENTING TICKET # 618

Plugged through: TBG

District: 04

Signed Ray Dinkel

KCC WICHITA

(TECHNICIAN)

CM

JAN 02 2018

RECEIVED

Form CP-2/3

DEC 18 2017

INVOICED
JAN 27 2018