

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-20225-00-00
Spot: SWSW Sec/Twnshp/Rge: 2-30S-19W
488 feet from S Section Line, 4762 feet from E Section Line
Lease Name: PARKIN Well #: 1
County: KIOWA Total Vertical Depth: 5076 feet

Operator License No.: 33388
Op Name: J. MARK RICHARDSON FAMILY TRUST
Address: 4050 N GOLDENROD CT.
MAIZE, KS 67101

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4670		WITH 2 SX CMT
CIBP		4850		WITH 2 SX CMT
PROD	5.5	5052	2615	WITH 250 SX CMT
SURF	8.625	616		WITH 660 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/18/2017 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: BILL SCHMIDT Company: RICHARDSON OIL Phone: (316) 755-3523

Proposed Plugging Method: CIBP @ 4850' & 4670' WITH 2 SX CMT EACH. PLUG AT 1320' WITH 12 SX GEL & 50 SX CMT PLUG AT 630' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: PARTIAL
Date/Time Plugging Completed: 12/18/2017 12:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4850' WITH 2 SX CMT. SET CIBP @ 4670' WITH 2 SX CMT. 1ST PLUG AT 1310' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 604' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 30 SX CMT. TOPPED OFF WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4974	4980		
4926	4928		
4922	4924		
4910	4912		
4828	4830		
4814	4818		
4720	4726		

INVOICED
JAN 17 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
DEC 27 2017
KCC DODGE CITY