

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-21680-00-00
Spot: NWSESENW Sec/Twnshp/Rge: 11-19S-25W
2019 feet from N Section Line, 2278 feet from W Section Line
Lease Name: BALDWIN Well #: 1-B
County: NESS Total Vertical Depth: 4423 feet

Operator License No.: 33605
Op Name: JOE GERSTNER OIL, LLC
Address: PO BOX 509
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1000		
PROD	5.5	4412	0	WITH 300 SX CMT
SURF	8.625	611		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/12/2017 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: PAT GERSTNER Company: JOE GERSTNER OIL Phone: (785) 798-0998

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT & 200# HULLS. PERFORATE TBG AT 1380' & SPOT 50 SX CMT & 100# HULLS. SET CIBP @ 1000' & PRESSURE TBG TO 500#. IF HOLDS PERFORATE AT 700' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 12/12/2017 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4380' & SPOT 35 SX CMT & 200# HULLS. PULLED TBG & PERFORATED AT 1680'. SPOTTED 50 SX CMT & 100# HULLS. PULLED TBG & SET CIBP @ 1000'. PRESSURED CASING TO 500#. HELD. PERFORATED AT 700'. TRIED TO PUMP INTO & COULD NOT. TOOK PRESSURE TO 2000#. RUN TBG TO 790' & PUMPED 95 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 5 SX CMT. TIED ONTO BACKSIDE & PRESSURED TO 500# RIGHT AWAY.

Perfs:

Top	Bot	Thru	Comments
4412	4423	OH	

INVOICED
JAN 17 2018

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
DEC 27 2017
KCC DODGE CITY