

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-10081-00-00
Spot: SWSWNE5W Sec/Twnshp/Rge: 25-27S-11W
1350 feet from S Section Line, 3915 feet from E Section Line
Lease Name: CUNNINGHAM UNIT B Well #: 2-35
County: PRATT Total Vertical Depth: 4066 feet

Operator License No.: 3880
Op Name: KC RESOURCES, INC.
Address: P. O. BOX 6749
SNOWMASS VILLAGE, CO 81615

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3447		
PROD	5.5	4050		225 SX
SURF	10.75	360		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/19/2017 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JIM KRAFT Company: _____ Phone: (785) 252-7030

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: SCOTT ALBERG WitnessType: PARTIAL
Date/Time Plugging Completed: 12/19/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

MR. KRAFT THINKS THERE IS A PLUG AT 3146' FROM AN OLD SERVICE REPORT, ALSO THINKS THE CASING WAS SQUEEZED AT 600'. 12/12/17 QUALITY WELL SERVICE TTOH (84 JOINTS). 12/13/17 EXCEL WIRELINE RAN INTO 2919' WITH CIBP. COULD NOT GET DOWN TO BOTTOM. RIG TTIH TO 3367', PUMPED 50 SX CLASS A CEMENT WITH 100 LBS HULLS TTOH, WAITED 3 HOURS RAN IN WITH WIRELINE TAGGED TOC @ 3160'. WIRELINE BONDLOGGED CASING FROM 1600' FEET TO SURFACE, FOUND CEMENT @ 630' TO 250'. WIRELINE PERFORATED @ 1460' & 900' & 235'. 12/14/17 RIG TTIH TO 1460' DISPLACED FLUID IN HOLE WITH 15 SX OF GEL, THEN SPOTTED 50 SX OF CLASS A CEMENT 3% CC, TTOH WAITED 2.5 HOURS TAGGED @ 1000' WITH WIRELINE. TTIH TO 90' SPOTTED 50 SX CEMENT, TTOH TO 235' CIRCULATED TO SURFACE WITH 45 SX CEMENT. TTOH, SWEDGE UP 5.5" CASING, OPENED SURFACE CASING VALVES AND CIRCULATED TO SURFACE WITH 105 SX CEMENT. 12/19/17 DUG HEAD OUT AND CUT OFF ADDED 4 SX OF CEMENT TO TOP OF 5.5" CASING, SURFACE CASING WAS STANDING FULL.

Perfs:

Top	Bot	Thru	Comments
3430	3439		

INVOICED
JAN 17 2018

Remarks:
Plugged through: CSG

District: 01

Signed B. J. Hope
(TECHNICIAN)

✓ SK