

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-21246-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 27-27S-5E  
4290 feet from N Section Line, 4290 feet from W Section Line  
Lease Name: FREEMAN Well #: 1  
County: BUTLER Total Vertical Depth: 2780 feet

Operator License No.: 30582  
Op Name: KISER, MICHAEL DBA MWK PETROLE  
Address: 508 STONE LAKE CT  
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2474		
PROD	5.5	2780	315	
PROD	5.5	2804		150 SX
SURF	8.625	201		130 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/22/2017 12:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: MIKE KISER Company: \_\_\_\_\_ Phone: (316) 734-4810

Proposed Plugging Method: LAY OUT TUBING & RODS, SAND 50' ABOVE PERFORATIONS AND PUT 5 SACKS OF CEMENT ON TOP OF SAND FOR BOTTOM PLUG. SHOOT OFF CASING AND LAY DOWN. BAIL WELL TO 250' AND SLURRY MIX CEMENT TO SURFACE. CLEAN UP LOCATION WHEN FINISHED.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/29/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Sanded well from 2474' - 2100'. Dump bailed 5 sxs cement on top of sand. Cut casing @ 315', layed down 8 ft 5.5" csg (315'). RIH w/ 4.5 bailer and bailed hole to 260' CMC poured 5 yd slurry mix to surface. (100 sxs slurry mix) cement at surface. Cement ticket # CMC 4014339

Perfs:

Top	Bot	Thru	Comments
2725	2736		
2170	2176		

INVOICED  
JAN 27 2018

Remarks:  
Plugged through: TBG

District: 02

Signed DUANE KRUEGER  
(TECHNICIAN)

