

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-067-00505-00-00
Spot: SESESENW Sec/Twnshp/Rge: 18-30S-35W
2760 feet from S Section Line, 2754 feet from E Section Line
Lease Name: JENNINGS M J Well #: 1-18
County: GRANT Total Vertical Depth: 2745 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2549	0	WITH 500 SX CMT
SURF	10.75	563		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/12/2017 12:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: JASON PHELPS Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: RUN TB GTO 2500' OR TOP OF FILL & SPOT 120 SX CMT WITH 300# HULLS. SET CIBP @ 600' WITH 2 SX CMT. PRESSURE TEST CASING TO 500#. RUN CBL TO FIND TOC. TOC BELOW THE 10 3/4" AT 563'. PERFORATE AROUND 590' & CIRCULATE CMT TO SURFACE LEAVING 7" AND THE ANNULUS FULL. TOC ABOVE IN THE 10 3/4" RTIH TO 600' & CIRCULATE 7" WITH CMT LEAVING IT FULL. FILL 10 3/4" X 7" ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/13/2017 10:00 AM KCC Agent: HEITH WALSH

Actual Plugging Report:

RTIH TAG TOP OF FILL AT 960'. SAND PUMPED AND CLEANED OUT TO 1348'. PRESSURE TESTED 7" TO 500#. RUN CBL FOR TOC. IT IS BELOW THE 10 3/4" SURFACE CASING. PERFORATE AT 1318' & PUMPED 50 SX CMT. PERFORATED AT 592' & CIRCULATED CEMENT TO SURFACE WITH 230 SX CMT FILLING 7" & 10 3/4" X 7" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
2539	2745		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed

Heith Walsh

(TECHNICIAN)

RECEIVED
DEC 27 2017
KCC DODGE CITY

Handwritten initials