

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-093-00614-00-00
Spot: NWSE Sec/Twnslip/Rge: 12-22S-36W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: STEENES Well #: 1
County: KEARNY Total Vertical Depth: 2860 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		930		
CIBP		2501		WITH 15 SX CMT
L1		2860		NOT CEMENTED
PROD 7		2630	0	WITH 100 SX CMT
SURF 10.75		225		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/19/2017 8:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: STAN COUCHMAN Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/19/2017 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2501' WITH 15 SX CMT. PLUG AT 2103' WITH 35 SX CMT. CIBP @ 930' TO COVER CASING LEAK. TEST 7" CASING TO 400#. HOLDING. RUN CBL FROM 920' TO 210'. TOP OF CMT AT 480'. PERFORATE 4 HOLES AT 300'. INJECTION RATE 2 BPM AT 200 PSI. RUN TBG TO 930' & SPOT 35 SX CMT. TOOH. CIRCULATE CMT TO SURFACE THROUGH PERF AT 300' USING 200 SX CMT LEAVING THE 7" CASING & 7" X 10 3/4" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2619	2705		

INVOICED
JAN 27 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

District: 01

RECEIVED
DEC 21 2017
KCC DODGE CITY

Signed

Ken Jehlik
5A

(TECHNICIAN)