

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-067-00210-00-00
Spot: SWSWSWNE Sec/Twnshp/Rge: 12-30S-36W
2726 feet from S Section Line, 2526 feet from E Section Line
Lease Name: DAVIDSON H B Well #: 1-12
County: GRANT Total Vertical Depth: 2725 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2517	0	WITH 125 SX CMT
SURF	10.75	575		WITH 100 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/07/2017 12:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: JASON PHELPS Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/07/2017 4:00 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

TAG TOP OF SAND AT 1251'. PERFORATE AT 1221'. TIH WITH TBG. SPOT PLUG AT 1231' WITH 50 SX CMT. TOOH WITH TBG. PUMPED DOWN 7" CASING AND CIRCULATED CMT TO SURFACE THROUGH CASING LEAK AT 719' TO 784'. FILLED 7" & 10 3/4" X 7" ANNULUS WITH 350 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2511	2516		
2489	2499		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed

[Signature]

(TECHNICIAN)

5A

RECEIVED
DEC 12 2017
KCC DODGE CITY