

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-21737-00-00  
Spot: NWSW Sec/Twnshp/Rge: 14-30S-7W  
1980 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: DUNKELBERGER B Well #: 2  
County: KINGMAN Total Vertical Depth: 4229 feet

Operator License No.: 4706  
Op Name: MESSENGER PETROLEUM, INC.  
Address: 525 S MAIN ST  
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4228	2790	100 SX
SURF	8.625	259		180 SX

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/20/2017 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JON F. MESSENGER Company: \_\_\_\_\_ Phone: (620) 532-5400

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/31/2017 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

QWS ARRIVED AT LOCATION. RAISED POLE, UNPACKED TUBING HEAD AND SET A BRIDGE PLUG AT 4040'. CAPPED WITH 25 SXS CEMENT, DUG CELLAR AND PIT, LINED PIT, UNPACKED CASING HEAD, SET FLOOR, CUT SURFACE OFF AT 4' BELOW GROUND. LOADED HOLE WITH FRESH WATER, RIPPED CASING AT 3045'. CASING CUTTER HUNG UP & PARTED SANDLINE, RAN SPEAR TO 2850', GOT HOLD OF CABLE, PULLED ON KNIFE, PULLED TUBING OUT, HAD 80' OF CABLE, RAN TUBING BACK IN TO 2500'. RETURNED NEXT DAY RAN TUBING TO 2900', GOT HOLD OF CABLE AND PULLED OUT TUBING. HAD 5' OF CABLE, RIGGED FLOOR BACK UP, TRIED TO WORK CASING FREE. LEFT ON TENSION. RETURNED NEXT DAY SHOT OFF AT 2790', PULLED CASING TO 130', PUMPED 20 SACKS GEL, PULLED CASING TO 1150' AND PUMPED 35 SACKS CEMENT, PULLED CASING TO 720', SWEDGED IN. RETURNED NEXT DAY, RAN BAYLOR IN AND TAGGED CEMENT AT 575', PRESSURED CASING TO 2000 PSI, NO GAIN, PULLED ONE JOINT, PRESSURED CASING TO 2000 PSI, NO GAIN. PULLED CASING OUT, RAN BAYLOR TAGGED CEMENT AT 850', RAN TUBING TO 725', PUMPED 35 SACKS CEMENT, PULLED TO 300', PUMPED 140 SACKS CEMENT TO SURFACE. PLUGGING COMPLETE.

Top	Bot	Thru	Comments
4096	4136		

INVOICED  
JAN 17 2018

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

JK