

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-20467-00-01
Spot: NWSENENW Sec/Twnshp/Rge: 2-34S-20W
4580 feet from S Section Line, 3290 feet from E Section Line
Lease Name: BAKER TRUST OWWO Well #: 1
County: COMANCHE Total Vertical Depth: 5250 feet

Operator License No.: 31652
Op Name: NORSTAR PETROLEUM, INC.
Address: 88 INVERNESS CIR E. UNIT F104
ENGLEWOOD, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4120		WITH 2 SX CMT
CIBP		4245		
PROD	4.5	5249	2004	WITH 400 SX CMT
SURF	8.625	661		WITH 500 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/12/2017 10:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4120' WITH 2 SX CMT. PLUG AT 860' WITH 10 SX GEL & 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 300' WITH 30 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/12/2017 11:20 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4120' WITH 2 SX CMT. 1ST PLUG AT 851' WITH 10 SX GEL & 40 SX CMT. 2ND PLUG AT 694' WITH 50 SX CMT. 3RD PLUG AT 315' WITH 30 SX CMT. 4TH PLUG AT 63' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4170	4194		


INVOICED
JAN 17 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
DEC 21 2017
KCC DODGE CITY

