

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-23429-00-00
Spot: SWNENENW Sec/Twnshp/Rge: 15-25S-13E
4935 feet from S Section Line, 3200 feet from E Section Line
Lease Name: ROGLIN Well #: R-16
County: GREENWOOD Total Vertical Depth: 1453 feet

Operator License No.: 6788
Op Name: NORDMEYER OIL, INC.
Address: 362 90TH RD
TORONTO, KS 66777

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD | 4.5 | 1453 | | 118 SX |
| SURF | 7.5 | 40 | | 12 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/18/2017 9:00 AM
Plug Co. License No.: 6788 Plug Co. Name: NORDMEYER OIL, INC.
Proposal Rcvd. from: RAY NORDMEYER Company: _____ Phone: (620) 637-2964

Proposed
Plugging
Method:

Per Instructions of the KCC

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 12/18/2017 12:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

Ran tubing to 1410', pumped 10 sxs cement, pulled tubing to 700', pumped 10 sxs cement, pulled tubing to 250', pumped 50 sxs cement to surface, gel spacers between cement plugs, casing shot @ 250' & 700',

RECEIVED
KCC DIST #3
DEC 20 2017
CHANUTE, KS

MH

INVOICED
JAN 17 2018

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. 3711
 Foreman Steve Mead
 Camp Eureka Ks

| Date | Cust. ID# | Lease & Well Number | Section | Township | Range | County | State | |
|--------------------------------|-----------|---------------------|----------------|----------|--------|-----------|--------|--------|
| 12-18-17 | 1212 | Roglin #16 | 15 | 255 | 13E | Greenwood | KS | |
| Customer Nordmeyer Oil Inc. | | | Safety Meeting | | Unit # | Driver | Unit # | Driver |
| Mailing Address 362 90th Rd | | | | | 102 | Rick | | |
| City Toronto | | | | | 113 | Alan | | |
| State KS | | | | | 141 | Tason | | |
| Zip Code 66777 | | | | | | | | |

Job Type PTA Hole Depth 1459 Slurry Vol. _____ Tubing 238 1410'
 Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left In Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting. Rig up to 2 3/8 Tubing Break Circulation w/ Fresh water.
Plug Well As Follow:

10 SKS AT 1410'
10 SKS AT 700'
30 SKS 260' TO SURFACE + TOP HALL OFF.
Total 50 SKS 60/40 PORMIX CEMENT 4% GEL

Job Complete Rigdown Thank You

| Code | Qty or Units | Description of Product or Services | Unit Price | Total |
|--|--------------|------------------------------------|------------|----------------|
| E105 | 1 | Pump Charge | 750.00 | 750.00 |
| C107 | 25 | Mileage | 3.95 | 98.75 |
| C202 | 50 SKS | 60/40 PORMIX CEMENT | 12.75 | 637.50 |
| C206 | 175# | Gel 4% | 120 | 35.00 |
| C206 | 200# | Gel Gel spacer | -20 | 40.00 |
| C198A | 2.15 Ton | Ton mileage bulk Trucks | m/c | 345.00 |
| C113 | 2 hrs | 80001 loc Trucks | 85.00 | 170.00 |
| | | | Sub Total | 2076.25 |
| | | | Sales Tax | 155.72 |
| Authorization by <u>Harry Nordmeyer</u> Title <u>Owner</u> | | | Total | <u>2231.97</u> |

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.