

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-00887-00-00
Spot: NESENW Sec/Twnshp/Rge: 23-31S-9W
1650 feet from N Section Line, 2310 feet from W Section Line
Lease Name: MARTIN B Well #: 1
County: HARPER Total Vertical Depth: 4475 feet

Operator License No.: 32825
Op Name: PIONEER EXPLORATION, LLC
Address: 15603 KUYKENDAHL STE 200
HOUSTON, TX 77090

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4100		
PROD	7	4475		250 SX
SURF	10.75	301		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2017 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: LARRY PRIEST Company: PIONEER EXPLORATION Phone: (620) 532-9461

Proposed Plugging Method: AS PER KCC RULES &: REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 03/24/2017 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

QWS MOVED IN. WENT IN HOLE WITH TUBING TO 4000'. PUMPED 110 SACKS CEMENT. PULLED UP AND WOC. TAGGED PLUG AT 3111'. PERFORATED AT 1500', 900' AND 351'. WENT IN HOLE WITH TUBING AND PACKER. PUMPED 75 SKS CEMENT AT 1500'. WOC. TAGGED PLUG AT 1330'. QWS MIXED AND PUMPED 50 SKS CEMENT AT 900'. WENT IN HOLE TO 351'. PUMPED 150 SKS CEMENT. PULLED OUT TUBING. TIED ONTO 7" CASING AND PUMPED 80 SKS DOWN CASING AND CIRCUALTED OUT SURFACE. CUT CASING OFF 4' BGL. TOPPED OFF WELL WITH 20 SKS CEMENT.

Perfs:

Top	Bot	Thru	Comments
4380	4386		
4140	4150		
4045	4079		
3284	3294		
3170	3180		

INVOICE


JAN 27 2017

Remarks:

Plugged through: TBG

District: 02

Signed _____



(TECHNICIAN)

SK