

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-20249-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 9-30S-9E
337 feet from S Section Line, 1989 feet from E Section Line
Lease Name: HYDE Well #: 17
County: ELK Total Vertical Depth: 1470 feet

Operator License No.: 4448 String Size Depth (ft) Pulled (ft) Comments
Op Name: PERKINS OIL ENTERPRISES, INC. PROD 5.5 1464 100 SX
Address: PO BOX 707 SURF 8.58 150 75 SX
HOWARD, KS 67349

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/11/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Revd. from: BUDDY FINNEY Company: Phone: (620) 505-0479

Proposed Plugging Method: Lay out tubing and packer; Run tubing to bottom and pump gel spacer; Pump at 50' cement plug; Pull up to 880'; Pump 50' cement plug. Pull up to 590' pump cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 12/11/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1350' gelled hole and spotted 8 sack plug. Pulled up to 1000' and spotted 8 sack plug. Pulled 1" and perforated casing at 550'. Ran 1" back into 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 138 sacks were used to plug this well.

RECEIVED
KCC DIST # 3
DEC 20 2017
CHANUTE, KS


DS INVOICED
JAN 27 2018

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC>

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)