

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-22005-00-00
Spot: E2SENE Sec/Twnshp/Rge: 11-17S-26W
3274 feet from S Section Line, 327 feet from E Section Line
Lease Name: DUMLER UNIT Well #: 10
County: NESS Total Vertical Depth: 4438 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1250		WITH 2 SX CMT
PROD	5.5	4438	0	WITH 150 SX CMT
SURF	8.625	245		WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/13/2017 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JASON RATLIFF Company: PICKRELL DRILLING Phone: (785) 798-5027

Proposed Plugging Method: TBG & RODS STUCK IN HOLE. TRY TO GET AS MUCH OUT OF HOLE. SET BOTTOM PLUG. PERFORATE AT ANHYDRITE & SPOT 50 SX CMT & 100# HULLS. SET CIBP @ 1250' WITH 2 SX CMT. PERFORATE AT 1150' & PUMP 50 SX CMT OVER CASING VOLUME. IF DOES NOT CIRCULATE PUMP 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/13/2017 3:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

TBG & RODS STUCK IN HOLE FROM 1900' TO BOTTOM. PERFORATED AT 1875' & SPOTTED 50 SX CMT & 100# HULLS. SET CIBP @ 1250' WITH 2 SX CMT. PRESSURED CASING TO 300#. PERFORATED AT 1150' & PUMPED 210 SX CMT. DID NOT CIRCULATE. TIED ONTO BACKSIDE & PUMPED 35 SX CMT. PRESSURED TO 300# & HELD. PULLED SWEDGE & TOPPED OFF WITH 20 SX CMT. CASING STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4438	4450		

MICHAEL MAIER
JAN 17 2018

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
DEC 27 2017
KCC DODGE CITY