

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-29595-00-01  
Spot: E2SESW Sec/Twnshp/Rge: 12-31S-15E  
660 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: GUTSCHENRITTER Well #: 12-24  
County: MONTGOMERY Total Vertical Depth: 1280 feet

Operator License No.: 35497  
Op Name: REDBUD OIL & GAS OPERATING, LLC  
Address: 16000 STUEBNER AIRLINE RD SUITE 3  
SPRING, TX 77379

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1280		157 SX
SURF	7	24		4 SX
T1	2.375	1252		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/20/2017 12:00 AM

Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP

Proposal Rcvd. from: AARON HAMMERSCHMID Company: \_\_\_\_\_ Phone: ( 6 ) 203-3170

Proposed Plugging Method: TIH w/ tubing to 1275'. Set cement plug from 1275' to surface. Cut off casing and restore location

Plugging Proposal Received By: DUANE SIMS

Witness Type: NONE

Date/Time Plugging Completed: 11/20/2017 12:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

TIH w/ 1270' 2 3/8" tubing, pumped 100 SKS cement. Tubing hung in hole. Pumped additional 120 SKS cement. Backed off tubing, recovered 7 joints (217') TIH w/ 275' of 1" tubing pumped 20 SKS cement, Good cement return to surface. Pulled 1" and topped off cement. (total of 240 SKS cement). Cut off casing and restored location.

Perfs:

Top	Bot	Thru	Comments
1255	1256		
1234	1235		
1233	1234		
1034	1236		
964	966		
963	965		
905	907		
871	879		

INVOICED  
JAN 17 2018

RECEIVED  
KCC DIST #3  
DEC 20 2017  
CHANUTE, KS


DS

Remarks: WELL WAS PLUGGED BECAUSE IT HAD BEEN SHUT IN FOR OVER 10 YEARS.

Plugged through: TBG

District: 03

Signed \_\_\_\_\_



(TECHNICIAN)