

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-20480-00-00
Spot: SESWNW Sec/Twnshp/Rge: 34-31S-10E
2957 feet from S Section Line, 4283 feet from E Section Line
Lease Name: K WALKER Well #: 1-A
County: ELK Total Vertical Depth: 2073 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2071		250 SX
SURF	8.625	107		85 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2017 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: ALAN NATION Company: _____ Phone: (620) 222-4304

Proposed Plugging Method: Set 20 sack cement plug at 1685' (above Ft. Scott perms 1700' to 1706'). Set 20 sack cement plug at 1222' (top of KC). Perforate 4.5" casing at 500' and circulate cement to surface.


Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 11/07/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran tubing down 4.5" casing to 1690' and set 25 sack cement plug above perms. Pulled tubing back to 1225' and set 20 sack cement plug at top of Kansas City. Perforated 4.5" casing at 507'. Ran tubing down to 512' and circulated 125 sacks of cement but did not completely fill the 4.5" casing and annulus. Came back five days later and filled the 4.5" casing from 35' to surface with eight sacks of cement. Also filled the annulus from 176' to surface by pumping 27 sacks of cement down one inch pipe.

Perfs:			
Top	Bot	Thru	Comments
1700	1706		
RECEIVED KCC DIST #3 DEC 26 2017 CHANUTE, KS			
DS INVOICED JAN 17 2018			

Remarks:
Plugged through: TBG

District: 03 Signed 
(TECHNICIAN)