

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-049-20456-00-00  
Spot: SWSENW Sec/Twnshp/Rge: 34-31S-10E  
2944 feet from S Section Line, 3646 feet from E Section Line  
Lease Name: KENNETH WALKER Well #: 2  
County: ELK Total Vertical Depth: 2332 feet

Operator License No.: 5120  
Op Name: RANGE OIL COMPANY, INC.  
Address: 9412 E. CENTRAL PO BOX 781775  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2332		350 SX
SURF	8.625	107		85 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/02/2017 12:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: ALAN NATION Company: \_\_\_\_\_ Phone: (620) 222-4304

Proposed Plugging Method: Set 20 sack cement plug at 1980' (above Miss perms 1996' to 200'). Set 20 sack cement plug at 1186' (top KC). Perforate 4.5" casing at 500' and circulate cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/02/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran tubing down 4.5" casing to 1980' and set 20 sack cement plug above perms. Pulled tubing back to 1200' and set 20 sack cement plug at top of Kansas City. Perforated 4.5" casing at 500'. Ran tubing down to 505' and circulated 90 sacks of cement which completely filled the 4.5" casing and annulus to surface. Cut casing off four feet below surface and welded plate on 8.625" casing.

Perfs:

Top	Bot	Thru	Comments
1996	2001		

RECEIVED  
KCC DIST # 3  
DEC 26 2017  
CHANUTE, KS

DS  
INVOICED  
JAN 17 2018

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)