

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-22294-00-00
Spot: SENWSE Sec/Twnshp/Rge: 34-31S-10E
1921 feet from S Section Line, 1764 feet from E Section Line
Lease Name: WALKER G Well #: 3
County: ELK Total Vertical Depth: 2310 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1720		
PROD	4.5	2308		175 SX
SURF	8.625	456		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/19/2017 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Revd. from: ALAN NATION Company: _____ Phone: (620) 222-4304

Proposed Plugging Method: As per State instructions

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 09/20/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran tubing down 4.5" casing to 1638' and set 20 sack cement plug above perfs. Pulled tubing out of casing. Perforated 4.5" casing at 1187'. Ran tubing down casing and set 20 sack cement plug at 1200'. Pulled tubing back uphole and filled 4.5" casing from 500' to surface with 100 sacks of cement. The backside of production casing had already be cemented from 500' to surface.

Perfs:

Top	Bot	Thru	Comments
2308	2310		
1676	1682		

RECEIVED
KCC DIST # 3
DEC 26 2017
CHANUTE, KS
INVOICE *DS*
JAN 27 2018

Remarks:
Plugged through: TBG

District: 03 Signed *D. Sims*
(TECHNICIAN)