

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-20481-00-01
Spot: SWSWNENW Sec/Twnshp/Rge: 34-31S-10E
4281 feet from S Section Line, 3633 feet from E Section Line
Lease Name: WALKER H Well #: 1
County: ELK Total Vertical Depth: 2301 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1700		
PROD	4.5	2300		220 SX
SURF	8.625	114		70 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2017 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: ALAN NATION Company: _____ Phone: (620) 222-4304

Proposed Plugging Method: As per State instructions

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 09/20/2017 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran tubing down 4.5" casing to 1638' and set 20 sack cement plug above perms. Pulled tubing back to 1168' and set 15 sack cement plug. Pulled tubing out of casing. Perforated 4.5" casing at 500'. Ran tubing down 4.5" casing to 500' and circulated cement on the inside and outside of casing and filled from 500' to surface with 185 sacks of cement. A total of 220 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1964	1970		
1654	1660		

RECEIVED
KCC DIST # 3
DEC 26 2017
CHANUTE, KS


DS
INVOICE
JAN 1 2018

Remarks:

Plugged through: TBG

District: 03

Signed _____



(TECHNICIAN)