

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-049-22291-00-00  
Spot: NESWSE Sec/Twnshp/Rge: 34-31S-10E  
1275 feet from S Section Line, 1739 feet from E Section Line  
Lease Name: WALKER G Well #: 1  
County: ELK Total Vertical Depth: 2298 feet

Operator License No.: 5120  
Op Name: RANGE OIL COMPANY, INC.  
Address: 9412 E. CENTRAL PO BOX 781775  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1750		
PROD	4.5	2296		328 SX
SURF	8.625	320		170 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/19/2017 12:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: ALAN NATION Company: \_\_\_\_\_ Phone: (620) 222-4304

Proposed Plugging Method: As per State instructions

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE  
Date/Time Plugging Completed: 09/20/2017 12:00 PM KCC Agent: DUANE SIMS

**Actual Plugging Report:**

Ran tubing down 4.5" casing to 1645' and set 20 sack cement plug above perms. Pulled tubing out of casing. Perforated 4.5" casing at 1194'. Ran tubing down casing and set 25 sack cement plug at 1200'. Pulled tubing back uphole and filled 4.5" casing from 500' to surface with 55 sacks of cement. The backside of production casing had already been cemented from 500' to surface. A total of 100 sacks of cement were used to plug this well.

**Perfs:**

Top	Bot	Thru	Comments
1669	1674		


RECEIVED  
KCC DIST # 3  
DEC 26 2017  
CHANUTE, KS  
DS  
INVOICE  
JAN 17 2018

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_



(TECHNICIAN)