

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-049-22293-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 34-31S-10E  
1363 feet from S Section Line, 1059 feet from E Section Line  
Lease Name: WALKER G Well #: 2  
County: ELK Total Vertical Depth: 2295 feet

Operator License No.: 5120  
Op Name: RANGE OIL COMPANY, INC.  
Address: 9412 E. CENTRAL PO BOX 781775  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2291		335 SX
SURF	8.625	329		170 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/21/2017 12:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: ALAN NATION Company: \_\_\_\_\_ Phone: (620) 222-4304

Proposed Plugging Method: As per State instructions

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/21/2017 12:00 PM KCC Agent: DUANE SIMS

**Actual Plugging Report:**

Ran tubing down 4.5" casing to 1600' and set 20 sack cement plug above perfs. Pulled tubing out of casing. Perforated 4.5" casing at 1191'. Ran tubing down casing and set 25 sacks cement plug at 1200'. Pulled tubing back uphole and filled 4.5" casing from 500' to surface with 70 sacks of cement. The backside of production casing had already been cemented from 500' to surface. A total of 115 sacks of cement were used to plug this well.

**Perfs:**

Top	Bot	Thru	Comments
2291	2295		
1670	1674		

RECEIVED  
KCC DIST # 3  
DEC 26 2017  
CHANUTE, KS

DS

INVOICED


JAN 17 2018

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_



(TECHNICIAN)