

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21537-00-00
Spot: SWNENENE Sec/Twnshp/Rge: 32-30S-18W
4887 feet from S Section Line, 524 feet from E Section Line
Lease Name: EMERSON CARAWAY TRUST Well #: 2
County: KIOWA Total Vertical Depth: 5125 feet

Operator License No.: 32781
Op Name: ROBERTS RESOURCES, INC.
Address: 2020 N TYLER RD, STE 106
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4970		WITH 2 SX CMT
CIBP	4.5	5048		
PROD	4.5	5120	2954	WITH 195 SX CMT
SURF	8.625	653		WITH 275 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 12/18/2017 9:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Revd. from: KENT ROBERTS Company: ROBERTS RESOURCES Phone: (316) 215-1683

Proposed Plugging Method: CIBP @ 4970' WITH 2 SX CMT. PLUG AT 1130' WITH 12 SX GEL & 50 SX CMT. PLUG AT 690' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/18/2017 11:20 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4970' WITH 2 SX CMT. 1ST PLUG AT 1128' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 688' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5058	5062		
5048			
5021	5027		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
DEC 21 2017
KCC DODGE CITY