

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-023-21406-00-00
Spot: SESWNENW Sec/Twnshp/Rge: 15-5S-37W
1219 feet from N Section Line, 1894 feet from W Section Line
Lease Name: DEEDS Well #: 1
County: CHEYENNE Total Vertical Depth: 5026 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4659		150 SX
SURF	8.625	348		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/18/2017 8:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: CLARK T SANDBERG Company: RAYMOND OIL COMPANY, INC. Phone: (31) 626-4214

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 400 # gel and 500 # hulls.
8 5/8" surface casing set at 348' w/350 sx cement.
4 1/2" production casing set at 4659' w/150 sx cement.
Port Collar set at 3095' was not cemented.
TD 5026'. PBTD 4609'.
Perforations: 4449' - 4455'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/19/2017 6:45 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Calculated casing stretch indicating 3200' pipe recovery. Set CIBP at 4400' w/2 sx cement placed on top with dump bailer. Loaded casing. Pulled into casing numerous times losing stretch. Recalculated stretch to 2700'. Perforated production casing at 3120'. Ran tubing to 3115' and pumped 50 sx cement w/100 # hulls. Pulled tubing to surface. Cut collars at 2287' and 2246'. Could not pull casing. Pulled 90,000 #. Ran tubing to 2250' and pumped 125 sx cement w/400 # hulls. Lost circulation. Pulled tubing to 640' and pumped 170 sx cement. Cement circulated to surface. Pulled tubing to surface. Connected to 4 1/2" casing and pumped 15 sx cement. Connected to 8 5/8" surface casing and pumped 20 sx cement. Pressured to 300 psi.

GPS: 39.62311N -101.46236W

Perfs:

Top	Bot	Thru	Comments
4449	4455		

INVOICED
JAN 17 2018

Remarks: ALLIANCE WELL SERVICE RIG AND OES PUMPING SERVICE LLC CEMENT TICKET # 54,985

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

KCC WICHITA

JAN 02 2018

RECEIVED

DEC 22 2017