

State of Kansas



15.145.20016.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bishop of Leben Drlg. has this
date requested permission to plug the following described well:

Mr. Bishop guarantees payment of the plugging fee.

Operator's full Name: Rock Island Oil & Ref. Co.

Complete Address: 321 West Douglas Wichita, Kansas

Lease Name: Fox Well No. 1

Location: NW NW NE Sec. 29 Twp. 20 Rge. 18 (E)(W) X

County Pawnee Total Depth 4110' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bishpp was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace
100 sc cement thru drill pipe. Heavy mud to 250' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Leo F. Mansing
Conservation Division Agent