

State of Kansas



15.145.20414.0000

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 28 1976

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Christopher of R & W Drlg. has this

date requested permission to plug the following described well:

Mr. Christopher guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Drlg. Co., Inc.

Complete Address: 435 Page Court, Wichita, Ks.

Lease Name: Smith Well No. 1

Location: S/2 NE NW Sec. 4 Twp. 20 Rge. (E)(W) 19

County: Pawnee Total Depth 4380' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Christopher was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 510' thru drill

pipe. Heavy mud to 300' set 25 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey  
Conservation Division Agent