

State of Kansas



15-145-20373-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Reddick of Damac has this

date requested permission to plug the following described well:

Mr. Reddick guarantees payment of the plugging fee.

Operator's full Name: Aspen Drlg., Co.

Complete Address: Box 783 Great Bend, Kansas

Lease Name: Buckman Well No. 1-14

Location: SE SW Sec. 14 Twp. 20 Rge. (E)(W) 18

County: Pawnee Total Depth 2230' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Reddick was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 435' and displace

50 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and

displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo T. Mansury
Conservation Division Agent