

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1963
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Drillers-Producers Pipe & Supply & C.S.O. Co
Complete Address: c/o Southwest Casing Pulling Box 364 Great Bend, Kans
Lease Name Hazlett Well No. B - 1
Location SW SE SE Sec. 11 Twp. 20 Rge. (E) (W) 20
County Pawnee Total Depth 4258
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Southwest Casing Pulling
Address: Great Bend, Kans License No. 399
Operation Completed: Hour 5:30PM Day 26 Month 11 Year 63

The Above well was plugged as follows:

8 5/8" 449' circulated with cement - 5 1/2" 4258' with 150 sax cement PB to 4239' Perf 4159'

Sanded back to 4100', set 4 sax cement with dump baller - pulled 2830'

5 1/2" to 600', circulated hole with heavy mud (21 sax Gel), displaced 20

sax cement through 5 1/2" at 600', heavy mud to 200', displaced 20 sax cement

through 5 1/2" at 200', heavy mud to 35', set bridge and filled to bottom

cellar with cement.

Mudding and cementing by Southwest Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edon Petty*
Well Plugging Supervisor

DATE 12/3/63
INV. NO. 8194-W