

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-145-20910.0000^N

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Anador Resources Inc

Complete Address 5700 S. Quibel #320 Englewood Colo 80111

Lease Name Hazlett Well No. 1-11

Location 1550' S - 1870' E Sec. 11 Twp. 20 Rge. 20 (East)(West)

County Pawnee Total Depth 4355

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Santa Fe Pully Co. Box 335

Address 403 W. Central Andover Mo. 67002 License No. _____

Operation Completed: Hour: 12:15 PM Day: 26 Month: 1 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows: 4% gel - 3% cc.

8 5/8" S.P. to 1118' w/ 250 SX cement + 250 SX 50/50 Potmix

Order: 130 SX 50/50 Potmix 4% gel - 3% cc + plug

1st plug @ 990' w/ 60 SX

2nd plug @ 420' w/ 50

3rd solid Bridge & Auto-plug @ 40' → cement 0' w/ 10 SX

5th Rat hole w/ 5 SX

6th Mousehole w/ 5 SX

cm by Sew

Amount of Surface Casing: 1118'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Steve [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

JAN 27 1982 1-27-82

CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE 2-4-82
INV. NO. 9208-W