

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 22 1978
3-22-78
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -145 -20,513 (of this well)

Operator's Full Name George A. Reed

Complete Address 645 4th Financial Center, Wichita, Kansas

Lease Name Seltmann Well No. 1

Location 100'E of C SW NE Sec. 10 Twp. 20 Rge. (E) (W) 20

County Pawnee Total Depth 4310'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor L. D. Drlg.

Address Great Bend, Kansas License No.

Operation Completed: Hour 3:40 P Day 19 Month 3 Year 1978

The above well was plugged as follows:

RTD 4310' 8 5/8 csg. set 297' cwc 225 sk. Flg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 3-23-78

INV. NO. 6986-W