

RECEIVED
STATE CORPORATION COMMISSION
Form CP-3
Rev. 1-4-68
MAR 06 1978
CONSERVATION DIVISION
Wichita, Kansas

R

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 145 - 20,510 (of this well)

Operator's Full Name Elk River Oil Co.

Complete Address Suite 300 Farmers & Bankers Bldg., Wichita, Kansas

Lease Name Dick Well No. 1

Location SW SE SW Sec. 15 Twp. 20 Rge. (E) (W) 20

County Pawnee Total Depth 4310'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 12 N Day 2 Month 3 Year 1978

The above well was plugged as follows:

RTD 4310' 8 5/8 csg. set 372' cwc 225 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 300' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. J. Massey
Well Plugging Supervisor

DATE 3-7-78

INV. NO. 6877-W