

KANSAS

FORM CP-3
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-145-20,733

245 North Water
Wichita, KS 67202

Operator's Full Name KANSAS PETROLEUM, INC.

Complete Address SUITE 100 - 200 EAST 1ST WICHITA, KS. 67202

Lease Name DICK Well No. #1

Location Q-SE-NW-SW Sec. 15 Twp. 20 Rge. 20 (East) (West)

County PAWNEE Total Depth 4340 FT.

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor HUSHY DRILLING CO. INC. (BILL ROACH)

Address 200 E-1ST SUITE 500-WICHITA, KS License No. _____

Operation Completed: Hour 12:45^{PM} Day 25 Month Nov Year 1980

The above well was plugged as follows:

8 5/8" 265 FT SP. CML w/200 ST 50/50 POZMIX-2% GEL-3% CA-CL.
ORDERED 110 ST 50/50 POZMIX 4% GEL. + 8 5/8" PLUG. - ELV. 2236 GL.
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
1ST PLUG. @ 680 FT w/70 ST CMT.
2ND PLUG. @ 240 FT w/25 ST CMT.
3RD PLUG. → SOLID BRIDGE HULL'S - PLUG. @ 40 FT 1/20 w/10 ST CMT.
5TH IN RAT HOLE

CEMENTED BY HALLIBURTON

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Murray Schmidt
Conservation Division Agent

DATE 12-11-80

INV. NO. 3732-W

RECEIVED
CORPORATION COMMISSION
NOV 26 1980
CONSERVATION DIVISION
Wichita, Kansas