

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 14 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Halliburton Oil Producing Company

Complete Address: 520 Cameron Bldg., Oklahoma City, Oklahoma 73106

Lease Name Dick Well No. 1

Location NW SE Sec. 15 Twp. 20 Rge. (E) (W) 20

County Pawnee Total Depth 4280

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Hellar Drlg.

Address: Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 2A Day 12 Month 4 Year 1969

The Above well was plugged as follows:

RTD 4280' 8 5/8 csg set at 211' cwc 150 sk. Gmt. Mat. 50-50 poz cmt. W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk cmt.  
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base  
of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Rev. J. Massey  
Well Plugging Supervisor

INVOICED  
DATE 4/14/69  
INV. NO. 9601-W