

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Citic Serv. Oil Co.
Complete Address: Box 308 - Guss Bend, Kansas.
Lease Name Risse C Well No. A3-n.
Location Ne-Nw Ne Sec. 14 Twp. 20 Rge. 20 (E) (W)
County Pawnee Total Depth 4299
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____
Plugging Contractor: Krijs Casing Pulling
Address: Chase Kansas. License No. 436
Operation Completed: Hour 5 Day 21 Month Feb Year 1966

The Above well was plugged as follows:

Total depth - 4299' - 8 5/8 at - 501 - (300 at) - 5 1/2 at 4299 - PB-4281
Perf 4202 - sand to 4190 and 5 of cement with dump bailer
Shot 5 1/2 at ~~4299~~³⁶⁸⁵ and pulled same out of hole - built
rock bridge at 480' and displaced 20 of cement - chunk mud
to 200' built rock bridge at 200' and displaced 20 of
cement - chunk mud to 40' built rock bridge and
displaced 10 of cement.

RECEIVED
CONSERVATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED FEB 23 1966

Signed: Gullus P. Leika
Well Plugging Supervisor

DATE 2/23/66
INV. NO. 2773-U
CONSERVATION DIVISION
Wichita, Kansas