

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Inc.
Complete Address 370 West Wichita Ave. Russell, Kansas
Lease Name George Miller Well No. 1
Location C SW NW Sec. 20 Twp. 20 Rge. (E) (W) 20
County Pawnee Total Depth 4372
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XX
Other well as hereafter indicated _____
Plugging Contractor Co. Tools
Address _____ License No. _____
Operation Completed: Hour 5:30 P Day 18 Month 7 Year 1971

The above well was plugged as follows:

RTD 4372' 8 5/8 osg setaat 231' cwc 150 sk Cmt. Mat. 50-50 poz W/4% gel
Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bro A. Massing
Well Plugging Supervisor

DATE 7-20-71
ENV. NO. 4032-W