

KANSAS

*Y* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
APR 24 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Charles Carlock

Complete Address 1515 Hillcrest, Newton, Kansas

Lease Name ~~Miller~~ KELLER TRUST Well No. 1

Location C NW NE Sec. 20 Twp. 20 Rge. (E) (W) 20

County Pawnee Total Depth 4352'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Woodman & Iannitti (Rotary)

Address        License No.       

Operation Completed: Hour 11 P Day 22 Month 4 Year 1972

The above well was plugged as follows:

RTD 4352' 8 5/8 csg set at 294' cwr Cmt. Mat. 50-50 poz cmt W/4% added gel.  
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *Leo A. Massey*  
Well Plugging Supervisor

INVOICED

DATE 4-27-72

INV. NO. 5634-W