

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson Oil Company

Complete Address 1425 Wichita Plaza Wichita, Kansas

Lease Name Wagner Well No. 1

Location C NE NE Sec. 17 Twp. 20 Rge. 20 (E) (W) X

County Pawnee Total Depth 4361

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour Day Month Year

The above well was plugged as follows:

Total Depth 4361 8 5/8 csg set at 299' cwc 175 sc.

5 1/2 csg set at 4357' cw 100 sc cement.

Filled with sand to (3600-3500) and dumped 5 sc cement with dump bailer.

Recov. 3188' of 5 1/2 csg.

Squeezed thru 8 5/8 plg container with 20 sc gel W/4 hulls. Pres. 800 lbs. Followed with 110 sc cement, 12 bbl gel, plg and 10 sc cement.

(0-50) cem. (50-250) gel (250-600) cement, 600 -TD gel and hulls.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Manning
Well Plugging Supervisor

DATE 1/24/68

INV. NO. 9135-4