

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 4 Twp. 20S Rge. 19 (W)

Location as "NE/CNW*SW*" or footage from lines. NE SW NW
Lease Owner. Jay-Bee, Jayhawk, H-30, Inc.
Lease Name. Smith Well No. 1
Office Address. 200 North Main, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed. September 13, 1965
Application for plugging filed. September 13, 1965
Application for plugging approved. September 13, 1965
Plugging commenced. September 13, 1965
Plugging completed. September 13, 1965
Reason for abandonment of well or producing formation. Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. Eldon Petty
Producing formation. Depth to top. Bottom. Total Depth of Well 4,350 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	291'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from rotary total depth (4,350') to 540'. Set bottom plug at 540' and cemented with 20 sacks cement and hulls. Filled hole with heavy rotary mud to 240'. Set second plug at 240' and cemented with 20 sacks cement. Filled hole with heavy rotary mud to 40'. Set top plug at 40' and cemented with 10 sacks cement - 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor. H-30, Inc.
Address. 200 North Main, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Merle Britting (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Merle Britting
200 North Main, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of September, 1965

My commission expires December 3, 1968.
Geraldine Hays, Notary Public.

15.145.30014.0000

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY Jay-Bee, Jayhawk, H-30, Inc.

SEC. 4 T. 20S R. 19W
 LOC. NE SW NW

FARM Smith NO. 1

TOTAL DEPTH 4,350'
 COMM. 9-3-65 COMP. 9-13-65
 SHOT OR TREATED
 CONTRACTOR H-30, Inc.
 ISSUED

COUNTY Pawnee
 KANSAS



CASING
 20 10
 15 8 5/8" 291' cem w/200 sx
 12 6
 13 5

2258 GL
 ELEVATION 2260 DF
 2263 KB
 PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil	15
Sand	60
Shale	200
Sand	225
Shale & Shells	292
Shells, Red Bed & Shale	1060
Red Bed	1415
Anhydrite	1455
Shale & Shells	2135
Shale & Lime	2335
Lime & Shale	2610
Shale & Lime	2720
Lime & Shale	3030
Shale & Lime	3332
Lime & Shale	3620
Shale & Lime	3732
Lime & Shale	3935
Lime	4130
Lime & Shale	4250
Shale & Lime	4310
Lime & Shale (Cherty)	4350

Electric Log Tops

Lansing	3787	-1524
Base K. C.	4086	-1823
Ft. Scott	4174	-1911
Cherokee Shale	4230	-1967
Pawnee Sand	4236	-1973
Cherokee Sand	4266	-2033
Mississippi	4346	-2083
Log T. D.	4349	-2086
Rotary T. D.	4350	-2087

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Merle Britting

STATE OF KANSAS }
 SEDGWICK COUNTY } SS:

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 17th day of September, 1965.

Geraldine Hays
 Geraldine Hays, Notary Public

My Commission Expires:
 December 3, 1968.